



# SCDOT Bridge Program Update

## July 2025

*Presented to the Carolinas AGC Summer  
Conference*

July 25, 2025




Josh Quattlebaum, PE  
State Bridge Construction Engineer

# Today's Topics


## Presentation Overview

- Bridge Team Organization
- Construction Program Overview
- Existing Inventory Conditions
- Bridge Funding
- Current Projects
- Future Projects
- Research Projects
- Specifications Update

# HQ Bridge Team



# District Construction Staff



## District 1

DEA – Robert Dickinson  
DCE – Jason Fulmer  
District Bridge – VACANT

## District 2

DEA – Kevin McLaughlin  
DCE – Mike Hannah  
District Bridge – Will Munnerlyn

## District 3

DEA – Brandon Wilson  
DCE – Josh Makison  
District Bridge – Tony Thompson

## District 4

DEA – Jason Johnston  
DCE – Melanie Mobley  
District Bridge – Tom Gaines

## District 5

DEA – Kyle Berry  
DCE – David Johnson  
District Bridge – Will Fulton

## District 6


DEA – Tim Henderson  
DCE – Daniel Burton  
District Bridge – Kevin Turner

## District 7


DEA – Brian Heape  
DCE – Lyle Davis  
District Bridge – Adam Bishop



# SCDOT Construction Program



# SCDOT Construction Program



# Bridges...





# 2025 Bridge Improvement Program




~ 60% of our inventory consists of slab bridges or bridge length culverts


# Existing Conditions

Posted

Closed









~2700 on  
timber piles

# Existing





# Existing Conditions



# FY 2026 Bridge Program Funding

Program	Funding Source	FY 2025 Budget
Bridge Reactionary Maintenance	State	\$30M
Bridge Preservation	Federal	\$23M
Inspection & Compliance	Federal	\$25M
Bridge Repair and Preventative Maintenance	Federal	\$45M
Individual Project Specific STIP Replacements	Federal	\$116M
		<b>Total = \$439M</b>

\$200 million in one time state funds received in FY 25 and again in FY 26



# Reactionary Maintenance - \$30 M

College Park Road - Berkeley



Fairforest Road - Spartanburg





# Preservation - \$23 M




# Inspection and Compliance - \$25 M





# Inspection and Compliance - \$25 M



# Bridge Packages

S-765 Hanging Rock Creek, BP 15



Package	Bid	District	Bridges
14	\$9.0 M	4	6 Sec.
15	\$13.4 M	2 & 4	4 Sec.
16	\$31.9 M	3	3 SC & 2 US
17	\$57.9 M	4	5 SC & 1 US
18	\$6.0 M	5	2 Sec.
19	\$23.9 M	3	8 Sec.
20	\$17.8 M	4	7 Sec.
27	\$10.8 M	5	1 Sec. & 1 SC
29	\$15.5 M	3 & 6	2 US
30	\$12.4 M	2,3,4	4 Sec.
31	\$12.9 M	3	4 Sec.
32	\$15.2 M	7	6 Sec.



# US-76 over the Wateree



- \$40.9 M Bid
- Bridge Length – 2310'
- 22 Spans of PSC Girders
- 42 Drilled Shafts
- Original Circa 1970



# I-20 over the Wateree

\$96.0 M Design  
Build Contract

Wateree Farm Pond Number Three

Wateree River Bridge (Eastbound)


Buck Creek

- 260' x 60' Three Span Girder Bridge over Farm Pond
- Eastbound Only

- 1515' x 98' River Bridge
- 11 Spans of PSC Girders
- 40 Drilled Shafts
- Original Circa 1970



# I-20 over the Wateree





# Old Vaucluse Road



# US-17 Waccamaw



Sep 24, 2024 at 2:21:59 PM  
Ocean Hwy  
Georgetown SC 29440  
United States

- Circa 1966
- >25,000 ADT
- Bridge Length = 2762'
- \$49.6 Emergency Procurement
- 24 New Drilled Shafts
- 6 Steel Plate Girders x 95'



# US-21 SCL RR in Chester County

Ultra High Performance Concrete (UHPC)








# UHPC Deck Overlay



# CFRP Strengthening

Asset ID: MJO Drawn By: 02/2021 Date Drawn:		 South Carolina Department of Transportation	
Checked by: MJC Date Checked: 03/2021		CFRP Slab Strengthening	



Epoxy-Coated, Fabricated, Unidirectional, High-Strength, Non-Woven Carbon Fiber Reinforcement (CFRP) Product Laminates for Structural Reinforcement Applications. Evaluated Per ICC-ACI 08.2C for Concrete Strengthening using Unidirectional, Non-Woven Carbon Fiber Reinforcement (CFRP) Systems.

Minimum Composite Gross Laminate Properties		
	Design Value (per ICC-ACI 08.2C)	Unit
Minimum Tensile Strength*	181,000	psi
Tensile Modulus	22,500,000	psi
Elongation at Break	0.006	in/in
Laminate Thickness	0.0472 in	in
Laminate Width	3.0 in	in

\* Primary Fiber Direction

FRP Table						
FRP Minimum Width	FRP Thickness	# Strips	# Layers	M <sub>u, FRP</sub> (k-ft)	Incremental FRP for Composite Truck	Incremental FRP for 100 Truck
(in)	(in)				(k-ft)	(k-ft)
3.0	0.0472	2	1	156.00	0.142	0.117
3.0	0.0472	3	1	186.00	0.210	0.169
3.0	0.0472	4	1	187.00	0.270	0.220
3.0	0.0472	5	1	186.00	0.280	0.221
3.0	0.0472	6	1	176.00	0.478	0.380
3.0	0.0472	7	1	186.00	0.587	0.459
3.0	0.0472	8	1	194.00	0.657	0.520

**Installation Procedures:**  
 Follow the More Stringent of the Manufacturers or the Following Installer Recommendations.

- 1) Installation shall only take place when Ambient and Substrate Temperatures are Between 40°F and 90°F.
- 2) Concrete shall be thoroughly prepared to achieve an Open-Pore Structure and Cleaned in accordance with ICC-ACI 08.2C, No. 2.1.2.1.2 to ensure of adequate adhesion. Application surfaces shall be clean, sound, and free of standing water at time of application. All dust, lubricants, greases, curing compounds, and other foreign materials that may hinder the bond must be removed before installation. Curing compounds and concrete surfaces must be thoroughly washed using approved epoxy primers or a suitable repair mortar in accordance with the manufacturer's instructions.
- 3) Apply the Paste Laminate before the Fiber Paste has Cured. Cut Laminate to Appropriate Lengths Using a Metal Cutting Wheel and Clean with Solvent to Remove all Contaminants.
- 4) Apply Approved Epoxy Paste to the Laminate Using a Paste Injector or Trowel to Form a Concave Groove. Section Profile with Peak Thickness of Approximately 1/8 in. at the Ends and 1/16 in. at the Edges. Press the Laminate into the Paste. Do not apply the Substrate and Remove Entrapped Air Using Hand Pressure. Rollers or Trowels will cause Fiber Failure to become Present.
- 5) Allow CFRP to Cure for 72 Hours before Applying Load on the Bridge.





Pi





# Upcoming Projects of Interest




# Bridge Package 21

1. S-197 over South Tyger River
2. S-51 over Snow Creek
3. S-133 over Little Cane Creek
4. S-168 over Trib. to Choestoea Creek
5. S-168 over Little Choestoea Creek

RFQ 6/30/25

Public Announcement January '26




# Bridge Package 22

## 13 Secondary Bridges in District 5

- Darlington (1)
- Florence (3)
- Georgetown (2)
- Horry (5)
- Marion (1)
- Williamsburg (1)

RFQ February '26

Public Announcement August '26






# Bridge Package 23

## 11 Secondary Bridges in District 6

- Berkeley (3)
- Charleston (5)
- Colleton (1)
- Dorchester (1)

RFQ August '26

Public Announcement February '27



# Long Point Road Interchange

To North  
Charleston

2 New Flyovers (1263' & 931')  
New 248' Bridge for Reloc. Line 4  
New 365' Bridge for Reloc. Line 1



Long Point Rd

Seacoast Pkwy

Wando Park Blvd


Belle Hall Pkwy

RFQ – June 13, 2025  
Announce Short List – Aug. 21, 2025

RFP for Industry Review – Sept. 19, 2025  
Public Announcement – May 2026



# Carolina Crossroads Phase 3D




RFQ – Sept. 2025

Public Announcement – Q3 2026

# I-26 MM 137-146

- Interchanges improvements at Exit 139 and 145 w/new bridges
- Replace 3 overpass bridges under close and detour:
  1. S-9-16 (Murph Mill Road)
  2. S-38-1304 (New Hope Road)
  3. S-38-166 (Waterspring Road)
- Replace mainline bridges over NSRR just before Exit 145
- New mainline bridges to replace culverts at Early Branch and Burke Creek
- Summer 2026 Tentative Letting





# Bridge Replacement/Repair Program

Letting Month	Replacements		Repairs/Rehabs	
	Contracts	Bridges	Contracts	Bridges
August '25	5	6	2	5
September '25	4	4	1	1
October '25	4	5	2	2
November '25	6	6	3	3
December '25	4	5	0	0
January '26	1	1	0	0
February '26	0	0	1	1
March '26	2	2	0	0
April '26	0	0	2	2
May '26	1	2	0	0
June '26	5	5	0	0
	32	36	11	14

# US-301 over Savannah River

## Existing Structure

- 1550' x 33.5'
- Circa 1965

## New Structure

- 1572' x 46.25'
- 3 Spans of Steel Plate Girders
- 8 Spans of 74" MBT
- 20 Drilled Shafts (84" Dia.)
- November 2025 Letting

Image © 2025 Airbus



# Research Projects

## Field Trials for Cost-Effective Strengthening of SC Load Posted Bridges

*Dr. Paul Ziehl, Univ. of South Carolina, 10/15/21 – 4/14/26*

Proposed research focuses on field trials of strengthening precast flat slab and precast channel bridges.

## Cost Effective Screening, Assessment, and Repair of Timber Piles



Dr. Brandon Ross, Clemson University, 5/15/24 – 11/15/27

Research objectives are to 1: Identify the causes, factors, and types of timber pile degradation, 2: Evaluate existing and novel means of screening, assessing, and analyzing timber piles, and 3: Evaluate the cost and technical effectiveness of timber pile screening, assessment, and analysis methods.

## Enhancing Structural Integrity of Aging Bridges in SC Using FRP

Approved, but not yet in progress

# 2025 Construction Specs





# 2025 Construction Specs











## SUPPLEMENTAL SPECIFICATIONS

[Roadway Design Home](#)[Construction Manual](#)[Standard Drawings](#)[Supplemental Specifications](#)[Supplemental Technical Specifications](#)[Standard Specifications](#)[Preconstruction Memos](#)[Preconstruction Advisory Memos](#)[Subscribe to Preconstruction Updates](#)

Note: All files are presented in a PDF Format.

[2007 Supplemental Specifications](#) | [2025 Supplemental Specifications](#)

### 2025 Supplemental Specifications

Title	Letting Date
<a href="#">Fuel Adjustment</a> 	01/25 - Present
<a href="#">Late Discovery of Archaeological Remains on Federal Aid Projects</a> 	01/25 - Present
<a href="#">Requirements for Fed Aid Contracts</a> 	01/25 - Present
<a href="#">Asphalt Binder Adjustment Index</a> 	01/25 - Present
<a href="#">Disadvantaged Business Enterprise (DBE)</a> 	01/25 - Present
<a href="#">Conquina Shell Base</a> 	07/25 - Present
<a href="#">Adhesively Bonded Anchors and Dowels</a> 	07/25 - Present
<a href="#">Construction Schedules</a> 	07/25 - Present
<a href="#">Pavement Preservation</a> 	07/25 - Present
<a href="#">On the Job Trainee</a> 	07/25 - Present

[Back to Top](#)

# 2025 Construction Specs





# Questions

